



WSP/OSPI Inspection Interpretations (September 2025)

1. Inspection Timeframes:

Summer: 3/15 — 8/31, Winter: 11/1 — 3/14.

2. Lighting:

It has been brought to our attention that some buses are arriving with lighting on both sides of the bus (see below) that does not meet our specifications. Some buses were inadvertently issued initial inspection forms with these lights on them before we became aware of them. These lights will need to be removed.



3. Pole Vaults:

- a. It is recommended that pole vaults be transported in “modified” exterior storage compartments whenever possible.
- b. Transporting pole vaults that are *securely* fastened (no bungee cords) underneath passenger seats next to the interior wall or to the outer seat legs is acceptable if no portion of the poles extend in front of an emergency exit or into the bus aisle.

